


Addendum No. 2

**DATE:** AUGUST 5, 2019  
**TO:** ALL PLANHOLDERS OF THE MORGAN HILL LIBRARY ADDITION  
**PROJECT**  
**FROM:** YAT CHO – PROJECT ENGINEER   
**RE:** CLARIFICATION

Page(s) 1.

1. The existing Fire Alarm Control Panel (FACP) is located in Telecom Room #127 and is Fire-Lite MS-9200UDLS.
2. Sheet E0.1 – Change light fixture M to be 3" Dia. X 12"H suspended decorative cylinder LED light fixture, 0.125 thick aluminum housing, cord/cable mount, standard beam, 1,000 lumens, 3000K, 0-10V dimming driver, 277V. Finish shall match existing. Field verify cable length. Manufacturer: Spectrum Lighting and Series: DC0312XT or approved equal.

ADDENDUM ACKNOWLEDGMENT

Bidder acknowledges receipt of this addendum, which shall be attached to the proposal.

\_\_\_\_\_  
Contractor's Representative

\_\_\_\_\_  
Date

**THIS DOCUMENT SHALL BECOME A PART OF THE PROJECT SPECIFICATIONS**