



Addendum No. 1

DATE: 02/04/21

TO: ALL PLANHOLDERS OF THE 2020 INFLOW AND INFILTRATION SEWER REPAIR PROJECT

FROM: YAT CHO – PROJECT ENGINEER

RE: BID OPENING INFORMATION AND CLARIFICATIONS

1. Under Notice Inviting Bids, Section 1 “Bid Acceptance”

I. The Bid Opening Date remains unchanged to “on or before Wednesday, February 17, 2021 at 11:00 a.m. at the Development Services Center office, located at 17575 Peak Avenue Morgan Hill, California.”

Bids may be mailed or dropped off anytime before 11:00 a.m. by the above date. The bid opening will be held on Zoom, see information below:

When: Feb 17, 2021 11:00 AM Pacific Time (US and Canada)

Register in advance for this meeting:

<https://us02web.zoom.us/meeting/register/tZMkceitqzMoH9RjPIpIXXAHJve-v1IsDu8Q>

After registering, you will receive a confirmation email containing information about joining the meeting.

2. Technical Specifications Section 01125-1.04.C, Bid Item Description for Bid Item No. 40 Shall be Replaced with the Following:

1. Clean Sewer, Remove Grease and Roots, and CCTV Inspect

The unit price bid per linear foot for this bid item shall constitute full compensation for all material, labor, equipment, tools, and services necessary to clean sewer, remove, and dispose of the existing grease and roots within the existing sewer mains, and complete CCTV inspection of existing sewer at the following locations:

- **SHEET C5, D5-C.MH.001 TO D5-A.MH.002, 470 LF**
- **SHEET C-19, G4-C.MH.005 TO C/O, 354 LF.**

The televising length included on the project drawings are measured from center of manhole to center of manhole. This price includes bypass pumping, site restoration, CCTV videoing, and other items as required to facilitate the construction of the work.

3. Technical Specifications Section 01120. The following section 1.14 shall be added:

1.14 CCTV INSPECTION AND CLEANING OF EXISTING SEWER MAINS

All sewer mains where improvements are being performed shall be CCTV inspected by the Contractor prior to construction per Section 02760. CCTV inspection videos shall be submitted to the City for review and approval a minimum of 2 weeks prior to construction at each location. Cleaning of the existing sewer mains will likely be required at all locations in order to obtain adequate CCTV inspections. The Contractor is responsible locating all proposed repairs and for confirming that the existing pipe condition is suitable for the proposed repairs and rehabilitations.

All sewer mains to be lined with Cured-in-Place Pipe (CIPP) shall be thoroughly cleaned and all roots shall be removed prior to CIPP installation. Cleaning procedures may require the use of mechanical equipment such as rodding machines, root cutters, porcupines, and high-velocity jet cleaners. No additional compensation will be provided for cleaning and root removal. Reference Section 02760 and 02900.

ADDENDUM ACKNOWLEDGMENT

Bidder acknowledges receipt of this addendum, which shall be attached to the proposal.

Contractor's Representative

Date

THIS DOCUMENT SHALL BECOME A PART OF THE PROJECT SPECIFICATIONS